

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21225-00-00
Spot: SENESESE Sec/Twnshp/Rge: 33-21S-19E
750 feet from S Section Line, 165 feet from E Section Line
Lease Name: BAILEY Well #: 1
County: ANDERSON Total Vertical Depth: 1228 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	0		0 SX
SURF	7	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2013 12:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: RUN WORKSTRING TO BOTTOM, CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP WELL OFF WITH CEMENT. TIE ONTO TUBING AND SQUEEZE CEMENT UNTIL DESIRED AMOUNT OF PRESSURE IS ACHIEVED. CUT WELL OFF 3' BELOW SURFACE.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 10/11/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

9/23/2013: HOOK ON TO CASING AND SQUEEZED CEMENT UNTIL PRESSURE INCREASES. PLACE RUBBER PLUG IN CASING AT 675 FEET. 10/11/2013: RUN 1-INCH TUBING TO 675 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT. A TOTAL OF 77 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

RECEIVED

MAR 27 2014

KCC Chanute Dist. #3

LS

KCC WICHITA

MAR 31 2014


RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)