

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20968-00-00

Spot: SESWSWSW

Sec/Twnshp/Rge: 15-22S-19E

165 feet from S Section Line, 4860 feet from E Section Line

Lease Name: BRECHEISEN

Well #: 1

County: ANDERSON

Total Vertical Depth: 852 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HWY 56

OWENSBORO, KY 42301

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
PROD	2.875	850		0 SX
SURF	6.625	50		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/26/2013 12:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Proposal Rcvd. from: STERLING BARKER

Company:

Phone: (785) 448-4816

Proposed
Plugging
Method:

Run workstring to bottom, cement to surface. Pull workstring out and top well off with cement. Tie onto well and squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.

Plugging Proposal Received By: LEVI SHORT

WitnessType: NONE

Date/Time Plugging Completed: 10/09/2013 12:00 AM

KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

9/26/2013: HOOK ON TO CASING AND SQUEEZED CEMENT UNTIL PRESSURE INCREASES. PLACE RUBBER PLUG IN CASING AT 740 FEET. 10/9/2013: RUN 1-INCH TUBING TO 740 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 500 POUNDS TO SHUT IN. A TOTAL OF 65 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

RECEIVED

MAR 27 2014

KCC Chanute Dist. #3

LS

KCC WICHITA

MAR 31 2014


RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed


4/04/14

(TECHNICIAN)