

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20595-00-00  
Spot: NWSESWSE Sec/Twnshp/Rge: 27-21S-19E  
4635 feet from N Section Line, 1654 feet from E Section Line  
Lease Name: KATTENHORN 1 Well #: 8-PN  
County: ANDERSON Total Vertical Depth: 755 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	755		75 SX
SURF	6.625	35		2 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/25/2013 12:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: TIE ONTO TUBING AND SQUEEZE CEMENT UNTIL PRESSURE STARTS TO CLIMB. INSERT CEMENT PLUG INTO TUBING AND PUSH PLUG DOWN TO 700'. RUN WIRELINE TO MAKE SURE PLUG IS AT 700'. LOG WELL. RUN WORKSTRING TO 700' AND PUMP CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP WELL OFF WITH CEMENT. CUT WELL OFF 3' BELOW SURFACE.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE  
Date/Time Plugging Completed: 10/21/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

9/25/2013: HOOK ON TO CASING AND SQUEEZED CEMENT UNTIL PRESSURE INCREASES. PLACE RUBBER PLUG IN CASING AT 580 FEET. 10/21/2013: RUN 1-INCH TUBING TO 575 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT THEN PRESSURE TO 500 POUNDS TO SHUT IN. A TOTAL OF 65 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
731	736		
RECEIVED (MAR 27 2014 KCC Chanute Dist. #3 LS			

Remarks:

Plugged through: CSG

KCC WICHITA  
MAR 31 2014  
RECEIVED

District: 03

Signed [Signature] (TECHNICIAN)  
4/04/14