

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-21913-00-00  
Spot: SWSESENW Sec/Twnshp/Rge: 3-22S-19E  
2827 feet from S Section Line, 3261 feet from E Section Line  
Lease Name: SETTLE Well #: 2P  
County: ANDERSON Total Vertical Depth: 854 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	852		110 SX
SURF	6	51		6 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/11/2013 12:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: RUN WORKSTRING TO BOTTOM, CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP WELL OFF WITH CEMENT. TIE ONTO TUBING AND SQUEEZE CEMENT UNTIL DESIRED AMOUNT OF PRESSURE IS ACHIEVED. CUT WELL OFF 3' BELOW SURFACE.

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE  
Date/Time Plugging Completed: 10/17/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

10/11/2013: HOOK ON TO CASING AND SQUEEZED CEMENT UNTIL PRESSURE INCREASES. PLACE RUBBER PLUG IN CASING AT 775 FEET. 10/17/2013: RUN 1-INCH TUBING TO 775 FEET AND FILL TO SURFACE WITH CLASS A PORTLAND CEMENT. A TOTAL OF 62 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

Top	Bot	Thru	Comments
816	843		

RECEIVED  
MAR 27 2014  
KCC Chanute Dist. #3  
LS  
KCC WICHITA

Remarks:

Plugged through: TBG

MAR 31 2014

RECEIVED

District: 03

Signed: [Signature]  
4/04/14 (TECHNICIAN)