

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21746-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 23-22S-19E
1234 feet from S Section Line, 5098 feet from E Section Line
Lease Name: THEXTON Well #: O-2
County: ANDERSON Total Vertical Depth: 0 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	0	0	SX
SURF	12	0	0	SX

** USE 750' FOR TD, PER PLUG, DETAILS BELOW, FOR INVCB. PWR*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2013 12:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: RUN WORKSTRING TO BOTTOM, CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP OFF WELL WITH CEMENT. RUN WORKSTRING DOWN BACKSIDE OF 2" TO THE TOP OF OLD CEMENT AND CEMENT TO SURFACE. PULL WORKSTRING OUT AND TOP OFF WITH CEMENT. TIE ONTO 2" AND SQUEEZE CEMENT UNTIL DESIRED AMOUNT OF PRESSURE IS ACHIEVED. CUT WELLOFF 3' BELOW SURFACE.

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 10/07/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:
HOOK ON TO 2-INCH CASING AND SQUEEZED CEMENT UNTIL PRESSURE INCREASES. PLACE RUBBER PLUG IN CASING AT 730 FEET. RUN 1-INCH TUBING TO 730 FEET INSIDE 2-INCH, 750 FEET INSIDE 6-INCH, AND 450 FEET INSIDE 10-INCH. USE EACH WORKSTRING TO FILL CASING TO SURFACE WITH CLASS A PORTLAND CEMENT. A TOTAL OF 360 SACKS OF PORTLAND CEMENT WERE USED TO PLUG THE WELL.

Perfs:

RECEIVED
MAR 27 2014
KCC Chanute Dist. #3
LS

KCC WICHITA
MAR 31 2014
RECEIVED

Remarks:
Plugged through: TBG

District: 03

Signed L. Short
4/04/14 (TECHNICIAN)