

J
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2-5-68
FEB 5 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued January 30, 1968.

Operator's Full Name E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Kansas 67202

Lease Name Ohlson Well No. # 2

Location C NW NW Sec. 8 Twp. 35 Rge. 12 (E) (W)W

County Barber Total Depth 5304'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 2:30PM Day 2nd Month February Year 1968

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cement circulated. 5300' of 4 1/2" long string,
cemented with 125 sacks. Plug back T.D. 4906'. Top perferation 4808'. Bottom
of the hole was sanded to 4775', and cemented with 4 sacks, through the
dump bailer, with cement from 4775' to 4725'. 3430' of 4 1/2" long string was
recovered from the hole. Fluid in the hole was bailed down to 265', bridge
plug and rock bridge from 265' to 255', and hole was filled with 4 yards
of ready-mix cement, with cement from 255' to the base of the cellar,

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/5/68

INV. NO. 7200-W

Signed: Archie Elving
Well Plugging Supervisor