

KANSAS

3
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 1967

8-4-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed July 18, 1967.

Operator's Full Name K & E Drilling, Inc.

Complete Address 719 Union Center Bldg., Wichita, Kansas 67202

Lease Name Farley-MacGregor Well No. # 1-4

Location C E/2 SE Sec. 4 Twp. 35 Rge. 14 (E) (W) W

County Barber Total Depth 4870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor K & E Drilling, Inc.

Address 719 Union Center Bldg., Wichita, Ks. License No.

Operation Completed: Hour 1:15 P.M. Day 1st Month August Year 1967

The above well was plugged as follows:

78' of 13 3/8" surface pipe, cement circulated. 776' of 8 5/8" surface
pipe, cement circulated with 375' sacks. Fluid level in the hole was at
350'. 1st cementing plug, bridged 2 sacks of dry cement and 1/2 sack of
hulls on fluid at 350', and cemented with 23 sacks with cement from 350'
to 265'. Hole was filled with drilling mud to 40'. 2nd cementing plug
bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40', and
cemented with 9 sacks with cement from 30' to the base of the cellar. Rat
hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

DATE 8/4/67
INV. NO. 6081-u