

15-007-00227-00-01

Form CP-3
Rev. 6-4-68

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1973
6-1-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Midwestern Supply Co Inc

Complete Address 207 Brown Bldg Wichita, KS

Lease Name C Molz Well No. 1

Location NW/NW/NW Sec. 8 Twp. 35 Rge. 14 (E) W

County Barber Total Depth 5658

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Oilfield Services

Address 107 W. Fowler Medicine Lodge, KS License No. 583

Operation Completed: Hour 11:00 AM Day 31 Month 5 Year 1973

The above well was plugged as follows:

187 ft 13' surface cement circulated. 4920 ft 4 1/2 long string cemented
with 130 sacks. Top perf. 4820 ft. Sand to 4800 ft, 4 sacks cement
with bailer. Pulled 3950 ft 4 1/2. Set 10 ft rock bridge at 175 ft,
40 sacks cement. Mud to 40 ft, 10 ft rock bridge, 20 sacks cement
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *Russell B. Bihart*
Well Plugging Supervisor

INVOICED

DATE 6/1/73
INV. NO. 7436-W

15-007-00227-00-01

S. NATHAN, JR.

#1 MOLZ (OWWO)

147
NW NW NW

Contr. SIERRA PET.

BARBER

County

E 1491 KB Comm.

Comp. 10/14/65

IP OF 2,200 MCFGPD

(MISS 4820-29 & 4843-46)

Tops	Depth	Datum
ELG	3755	-2264
HEEB	3960	-2469
TOR	3985	-2494
LANS	4146	-2655
DET MISS	4797	-3306
CH MISS	4822	-3331
KIND	5124	-3633
CHAT	5208	-3717
MAQ	5252	-3761
VIO	5276	-3785
SIMP	5428	-3937
ARB	5607	-4116
TD	5658	-4167

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Casing
13" 187
WAS: WM. GRUENERWALD #1 MOLZ,
D & A. 7/27/56:
DST 4828-48/2', 70' GCM; SPKS O,
BHP 1765#:
DST 4850-72/1', 10' M, SPKS O,
BHP 25#:
DST 4870-4920/2', 1080' GCM, 540'
MDY SW, BHP 1815#:
NEW INFO: CO 4920; 4" 4920/130 SX;
4/4843-46: A 250 (15%) ACID FRAC
(15,000 JEL A) FLO IN EXCESS OF 20
BBLS FLUID PER DAY; CP 1000#, FP
AETNA GAS 400#, 15/64" CK, TST 1/4
MCFGPD, FRAC (40,000 GW
+ 200# MOTH BALLS) PE
4820-29; FRAC (65,000 GW)
SWB LD: HAD INCR IN GAS;

+	+	+
+	+	+
+	+	+

Powers

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1973
5-18-73
CONSERVATION DIVISION
Wichita, Kansas