

15-007-20051-0000

Form CP-3  
Rev. 6-26-62

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

FEB 26 1968

CONSERVATION DIVISION  
Wichita, Kansas  
2-26-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed February 7, 1968.

Operator's Full Name Western Oil Fields, Inc.

Complete Address: P. O. Box 791, Ponca City, Oklahoma 74601

Lease Name Sternberger Well No. # 5

Location C SE NW SE Sec. 10 Twp. 35 Rge. 14 (E) (W) W

County Barber Total Depth 4910'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Ks. 67202 License No.     

Operation Completed: Hour 11:15 AM Day 23rd Month February Year 1968

The Above well was plugged as follows:

387' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole was  
filled with drilling mud to 300', 1st cementing plug, bridged with 1 sack  
of dry cement and 1/2 sack of hulls on fluid at 300', and cemented with 24  
sacks, with cement from 290' to 215'. Hole was filled with drilling mud  
to 40', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack  
of hulls, and cemented with 9 sacks, with cement from 30' to the base of  
the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 2/26/68  
INV. NO. 4306-W