

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 1 1974  
3-1-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don Rider Production

Complete Address 104 W Lockwood, Medicine Lodge, KS

Lease Name Sternberger Well No. 4

Location NW/NE/NE Sec. 12 Twp. 35 Rge. 14 (E) (W) W

County Barber Total Depth 4970

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 2:00 PM Day 28 Month 2 Year 1974

The above well was plugged as follows:

346 ft 8 5/8 surface cemented with 350 sacks. 4970 ft 5 1/2 long string  
cemented with 100 sacks. Top perf. 4890 ft. Sand to 4800 ft, 5  
sacks cement with bailer. Pulled 4000 ft 5 1/2. Set 10 ft rock bridge  
at 250 ft. Fill hole with 4 yds redimix to surface.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 3/1/74  
INV. NO. 8674-W

Signed [Signature]  
Well Plugging Supervisor