

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21004

LEASE NAME Ohlson

WELL NUMBER 1

SPOT LOCATION N/2 NE SE

SEC. 9 TWP. 35S RGE. 12 (E) or (W)

COUNTY Barber

Date Well Completed 1/9/81

Plugging Commenced 11/6/86

Plugging Completed 11/25/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR McGinness Oil Co.

ADDRESS 1026 Union Center Bldg., Wichita, KS 67202

PHONE # (316) 267-6065 OPERATORS LICENSE NO. 5255

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed?                      If not, is well log attached? was

Producing formation                      Depth to top                      bottom                      T.D. 4876

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	327	None
				4 1/2	4875	3800

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Sand from 4861 to 4800 4sx cement with dump bailer - Sun pump in 3sx hull, 15sx gell, 50sx cement, 10sx gell, 1sx hull, plug, 100sx cement 60-40 POZ

Metz and E. Morgenstern on location  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Elmo Morgenstern*  
(Address) Medicine Lodge, KS 67104  
SUBSCRIBED AND SWORN TO before me this 25 day of November, 1986

State of Kansas - Notary Public  
**GLENDA MORRISON**  
My Appt. Exp. 5-9-90

DEC 01 1986

*Glenda Morrison*  
Notary Public

My Commission expires: May 9, 1990

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

COPY


API No. 15 — 007 — 21,004-0000  
County Number

S. 9 T. 35S R. 12<sup>XX</sup> W

Loc. M/2 NE SE

County Barber

640 Acres  
N



Locate well correctly  
Elev.: Gr. 1421'

DF KB 1426'

Operator **McGinness Oil Company**

Address **1026 Union Center Bldg. Wichita, KS 67202**

Well No. **1** Lease Name **Ohlson "B"**

Footage Location  
300 feet from (N) <sup>XX</sup> line feet from (E) (W) line

Principal Contractor **Slawson Drilling - Rig #5** Geologist **Douglas H. McGinness II**

Spud Date **10/23/80** Date Completed **1/09/81** Total Depth **4876'** P.B.T.D. **4861'**

Directional Deviation Oil and/or Gas Purchaser **Koch Oil**

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	24#	327'	Common	250	2% gel, 3% C.
Production	7 7/8"	4 1/2"	10 1/2"	4875'	Common	100	2% gel, 3% C.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			4		4841-4848'
Size	Setting depth	Pecker set at			
2 3/8"	4835'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1500 gallons of Acid - 15% HCL	4841'-4848'

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.) **Pumping**

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	25 bbls.	MCF	65 bbls.	CFPB

Disposition of gas (vented, used on lease or sold) **Koch Oil** Producing interval(s) **See Above**

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

556 MJK