

15-007-00161-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County, Sec. 8 Twp. 35S Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SE SE

Lease Owner Flynn Oil Co. - Barbour Drilling Co.

Lease Name Leonard Achenback Well No. 1

Office Address Utica National Bank Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 12-11 1955

Application for plugging filed 12-11 1955

Application for plugging approved 12-11 1955

Plugging commenced 12-11 1955

Plugging completed 12-11 1955

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Murial Rives

Producing formation Depth to top Bottom Total Depth of Well 5670 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	275'	8-5/8"	275'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 280'. Pushed 1/4 sack of hulls and a wooden plug to 280'. Spotted 20 sacks of cement on top of wooden plug. Filled hole with heavy mud to 35'. Pushed 1/4 sack of hulls and wooden plug to 35'. 10 sacks of cement on top of plug to top of surface pipe. Welded cover on top of surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Co.

Address 1612 First National Building, Tulsa 3, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa, ss.

E. W. Pribyl (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BARBOUR DRILLING COMPANY

(Signature) E. W. Pribyl

1612 First National Building, Tulsa 3, Okla. (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 55

My commission expires July 27, 1957

Merry Jane Burt Notary Public.

STATE CORPORATION COMMISSION

DEC 23 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 8 T 35 R 12 W
BOOK PAGE 33 LINE 20

15-007-0016-0000

LEONARD ACHENBACK NO. 1

SW SE SE Section 8-35S-12W
Barber County, Kansas
Flynn Oil Company

8-5/8" O. D. casing cemented at 287'

Drilling commenced November 13, 1955
Drilling completed December 11, 1955

FROM	TO	FORMATION	REMARKS
0'	95'	Clay & sand	
95	185	Sand & shale	
185	475	Red bed	8-5/8" O. D. casing cemented with 250 sacks cement at 287'
475	1700	Shale & shells	
1700	1820	Lime & shale	
1820	2400	Lime	
2400	2630	Lime & shale	
2630	3217	Shale & lime	
3217	3363	Lime	
3363	3515	Lime & shale	
3515	3732	Shale	
3732	3790	Sand	
3790	3885	Sand & shale	
3885	3940	Lime & shale	
3940	3985	Lime	
3985	4060	Lime & shale	
4060	4150	Shale & lime	
4150	4345	Lime & shale	
4345	4420	Shale, sand & lime	
4420	4513	Shale & lime	
4513	4570	Chert & lime	
4570	4655	Lime & shale	
4655	4740	Lime	
4740	4780	Lime & shale	
4780	4825	Lime, shale & sand	
4825	4847	Lime & shale	
4847	4935	Chert	
4935	4974	Lime & chert	
4974	5014	Lime	
5014	5163	Shale & lime	
5163	5215	Shale, lime & chert	
5215	5256	Shale & lime	
5256	5292	Lime & shale	
5292	5385	Lime & chert	
5385	5396	Lime & shale	
5396	5422	Shale	

PLUGGING
 WELL SEC-8-135-R12W
 BOOK PAGE-23 LINE 20

12-17-55

FROM	TO	FORMATION	REMARKS
5422	5435	Sand	
5435	5478	Shale & lime	
5478	5494	Lime & sand	
5494	5530	Sand & lime	
5530	5546	Sand & shale	
5546	5589	Shale & lime	
5589	5625	Lime & sand	
5625	5640	Shale & lime	
5640	5670	Lime & sand	
T.D. 5670'			Dry hole - well plugged

This is a true copy of the driller's log as shown on the drilling tickets.

BARDOUR DRILLING COMPANY

By E. W. Driggs

Subscribed and sworn to before me on this 12th day of December, 1955

Merry Jane Burt
Notary Public

My commission expires: July 27, 1957

PLUGGING
FILE SEC 8 T. 35 R. 13 W.
BOOK PAGE 23 LINE 20

12-17-55