

WELL PLUGGING RECORD

State Of Kansas
State Corporation Commission
130 S. Market, Room 2078
Wichita, KS 67202

Lease Operator: Petroleum Property Services, Inc.
155 N. Market #1000, Wichita, KS 67202
Phone 316-265-3351
Character of Well: OIL

API Number: 15-007-01318-00-00
Lease Name: DAVIS RANCH
Well Number: 2-12
3960 Ft. From S Section Line
3960 Ft. From E Section Line
Sec: 12 TWP: 35S RGE: 15W
Operators License No. 31142 BARBER County:
Date Well Completed: 10/19/62
Plugging Commenced: 10/12/00
Plugging Completed: 10/13/00

The plugging proposal was approved on: 9/6/00

by: MICHAEL MAIER

KCC District Agent

Is ACO-1 Filed: NO If not, is well log attached? YES

Producing Formation: MISSISSIPPI Depth to Top Bottom T.D.
CHEROKEE M-5004,C-4946 M-5005,C-4950 5025

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MISSISSIPPI OIL		5004	5005	8 5/8	1015	0
CHEROKEE OIL		4946	4950	4 1/2	5024	1090

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or plugs were used, state the character of same and depth place, from ___ feet to ___ feet each set. CAST IRON BRIDGE PLUG @ 4900 W/4 SX CEMENT ON TOP WITH DUMP BAILER. PULL 1090' CASING, RUN 2" TBG TO 1020' LOAD HOLE W/15 SX GEL, PUMP 50 SX 60/40 CEMENT. PULL TBG TO 400'. PUMP 40 SX 60/40 CEMENT. PULL TBG TO 40' AND FILL TO SURFACE W/10 SX 60/40 CEMENT. HOLE STAYED FULL.

Name of Plugging Contractor: QUALITY WELL SERVICE
Address: 415 EAST MAIN, STERLING, KS 67579

License No. 31925

Name of Party Responsible For Plugging Fees: Petroleum Property Services, Inc.

STATE OF: KANSAS COUNTY OF: SEDGWICK, SS.
R.J. Thatcher (Employee of Operator) or (Operator), of above-
described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements,
and matters herein contained and the log of the above-described well as filed that the same are true
and correct, so help me God.

Signature: RJ Thatcher
Address: 3535 American Drive, Colorado Springs, CO 80917

SUBSCRIBED AND SWORN TO before me this 8th day of Nov., 2000



Rosann M. Schippers
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

My Commission Expires: 9/28/03



NOV 9 2000
11-9-00
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Braden Drilling, Inc.
 DAVIS RANCH #2-12
 C NW NW Sec. 12-35-15W
 Barber County, Kansas

Commenced: October 3, 1962


Completed: October 19, 1962

Set 8 5/8" at 1015' and cemented with
 700 sacks cement.

Set 4 1/2" at 5024' and cemented with
 140 sacks cement.

Clay	350 feet
Red bed	650
Shale and shells	1850
Lime shells and shale	1900
Shale and shells	1975
Lime	2300
Lime and shale	2465
Lime	2635
Lime and shale	3975
Shale	4005
Lime and shale	4120
Lime	4910
Lime and shale	4956
Sand and shale	4979
Lime	5025 Total Depth


I hereby certify that this is a true and correct log of the above captioned well, as shown by the daily drilling reports.



F. M. Callaway

Subscribed and sworn to before me this 25th day of October, 1962.

My commission expires March 21, 1966


 Helen Schultz, Notary Public

ALLIED CEMENTING CO., INC.

4241

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

15-007-01318-0000

SERVICE POINT

Med Lodge

DATE <i>10-12-06</i>	SEC. <i>12</i>	TWP. <i>35S</i>	RANGE <i>15 W</i>	CALLED OUT <i>9:00 AM</i>	ON LOCATION <i>10:30 AM</i>	JOB START <i>11:00 AM</i>	JOB FINISH <i>12:00 PM</i>
LEASE <i>Davis Ranch</i>		WELL # <i>2-12</i>	LOCATION <i>Hardtner 15 W</i>	<i>Go past</i>		COUNTY <i>Barber</i>	STATE <i>KS</i>
OLD OR NEW (Circle one) <input checked="" type="radio"/> OLD		<i>2nd cattle guard 1 W 1/2 into</i>					

CONTRACTOR *Quality Well Service* OWNER *PPSI*
 TYPE OF JOB *OHP*

HOLE SIZE	T.D.
CASING SIZE <i>8"</i>	DEPTH <i>1020</i>
TUBING SIZE <i>2 3/8"</i>	DEPTH <i>1020</i>
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT
 AMOUNT ORDERED *110 SX 60-40-6*
15 SX gel

COMMON	<i>66</i>	@	<i>6.35</i>	<i>419.10</i>
POZMIX	<i>44</i>	@	<i>3.25</i>	<i>143.00</i>
GEL	<i>21</i>	@	<i>9.50</i>	<i>199.50</i>
CHLORIDE		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>131</i>	@	<i>1.05</i>	<i>137.55</i>
MILEAGE	<i>131 x 40</i>		<i>.04</i>	<i>209.60</i>

TOTAL *1108.75*

EQUIPMENT

PUMP TRUCK	CEMENTER	<i>Justin Hart</i>
# <i>233-302</i>	HELPER	<i>Shane Winsor</i>
BULK TRUCK	DRIVER	<i>David Felio</i>
# <i>272</i>		
BULK TRUCK	DRIVER	
#		

REMARKS:

loged hole 15 sx gel
50 SX 1020,
40 SX 409,
20 SX 40

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE				<i>470.00</i>
EXTRA FOOTAGE		@		
MILEAGE	<i>40</i>	@	<i>3.00</i>	<i>120.00</i>
PLUG		@		
		@		
		@		

TOTAL *590.00*

CHARGE TO: *PPSI*
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@			
	@			
	@			
	@			
	@			

Perf-Tech

Wireline Services

15-007-01318-0000

1652

P.O. Box 87
Hays, KS 67601-0087

Job Ticket

DATE Oct 9 '00

CHARGE TO PPST

ADDRESS _____

LEASE AND WELL NO. Davis Ranch 2-12 FIELD _____

NEAREST TOWN _____ COUNTY Barber STATE Ks

CUSTOMER'S ORDER NO. _____ SEC. 12 TWP. 35S RANGE 15W

ZERO 10 ft ALL CASING SIZE 4 1/2 WEIGHT _____

CUSTOMER'S T.D. _____ PERF TECH T.D. _____ FLUID LEVEL _____

ENGINEER Bill Kla OPERATOR Dean F

PERFORATING					
CODE REFERENCE	DESCRIPTION	NO HOLES	DEPTH		AMOUNT
			FROM	TO	

PLUGS, PACKERS AND OTHER					
CODE REFERENCE	MFG. TYPE	CASING		DEPTH	AMOUNT
		SIZE	WEIGHT		
74100	Klaus	4 1/2	12	4700	980
74200	Tool				150
74300	Alpha	4 1/2	11.2	4700	640

TRUCK RENTAL			
CODE REFERENCE	RUN NO.	PREVIOUS INVOICE NO.	AMOUNT
702.55	On-		680

DEPTH OF OPERATIONS CHARGES					
CODE REFERENCE	FROM	TO	NO. FEET	PRICE PER FT.	AMOUNT

Disc Price **SUB TOTAL** 1200

TAX

PLEASE PAY FROM THIS INVOICE TOTAL

[Handwritten signature]

RECEIVED THE ABOVE SERVICE ACCORDING TO THE TERMS AND CONDITIONS SPECIFIED BELOW WHICH WE HAVE READ AND TO WHICH WE HEREBY AGREE

Customer Richard O. McIntyre

\$ 1276.80

General Terms and Conditions

- (1) All accounts are to be paid within the terms fixed by Perf-Tech invoices; and should these terms not be observed, interest at the rate of 1.5% per month will be charged from the date of such invoice.
- (2) Because of the uncertain conditions existing in a well which are beyond the control of Perf-Tech, it is understood by the customer that Perf-Tech cannot guarantee the results of their services and will not be held responsible for personal or property damage in the performance of their services.
- (3) Should any of Perf-Tech instruments be lost or damaged in the performance of the operations requested, the customer agrees to make every reasonable effort to recover same, and to reimburse Perf-Tech, for the value of the items which cannot be recovered, or the cost of repairing damage to items recovered.
- (4) It is further understood and agreed that all depth measurements shall be supervised by the customer or its employees and customer hereby certifies that the zones, as shot were approved.