

15-159-03264-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rice County. Sec. 1 Twp. 19 Rge. (E) 10 (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines SW SE NE

Lease Owner Westgate-Greenland Oil Company

Lease Name Behnke Well No. 1

Office Address 1022 Union National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 6-14-48 19

Application for plugging filed 6-14-48 19

Application for plugging approved 6-17-48 19

Plugging commenced 6-14-48 19

Plugging completed 6-15-48 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well C D Stough

Producing formation Depth to top Bottom Total Depth of Well 2983 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	171	10 3/4"	171	none


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 2983 to 165 feet

Set plug at 165' and cemented with 20 sacks cement

Filled hole to 25' with heavy mud.

Set plug at 25' and dumped in 15 sacks cement to cellar base.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. E. Bitler, 1022 Union National Bank Building
Address Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler


1022 Union National Bank Building, Wichita 2, Ks
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of June, 19 48

Esther Russell

Notary Public.

My commission expires May 25, 1949



COMPANY: Westgate Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 WELL: Behnke #1
 LOCATION: SW SE NE Section 1-19-10W
 Rice County, Kansas
 ELEVATION: 1716
 COMMENCED: June 3, 1948
 COMPLETED: June 14, 1948

0	to	100	Clay sand & line rock
100	to	150	Sand stone & shale
150	to	235	Shale & shells
235	to	465	Shale & red rock
465	to	500	Anhydrite
500	to	510	Shale & shells
510	to	640	Red bed
640	to	710	Shale & shells
710	to	890	Shale
890	to	1295	Shale & shells
1295	to	1380	Shale & lime
1380	to	1595	Lime
1595	to	1705	Lime & shale
1705	to	1820	Lime
1820	to	1945	Shale & Lime
1945	to	1960	Lime
1960	to	2315	Lime & shale
2315	to	2415	Lime
2415	to	2470	Shale & lime
2470	to	2750	Lime
2750	to	2920	Lime & shale
2920	to	2979	Lime
2979	to	2983	Lime soft
		2983	T. D.

Set 171 feet 10 3/4" casing - cemented with 125 sacks cement

Tops: Lansing - 2824

Dry & abandoned

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Behnke #1, Section 1-19-10W, Rice County, Kansas as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 23th day of June, 1948.

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November 30, 1950

