


JUL 19 1974
7-19-74
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Attachments
Mail or Deliver Report to
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Barber County, Sec. 10 Twp. 25 Rge. 15 (E) (W)
Location at "NE/SW/SE" or footage from lines NE SE NW
Lease Owner Braden Deem, Inc.
Lease Name Davis Ranch 1-10 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 6/25/74 19
Plugging completed 7/12/74 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 5070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	890	none
				4 1/2"	5046	3205'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 5070', ran sand to 4900' and ran 3 sacks cement.
Shot pipe at 4571', 4455', 4308', 4215', 4010', 3857', 3736',
3649', 3507', 3414', 3320', 3215', pulled pipe. Set 10' rock
bridge at 200' and ran 25 sacks cement. Mudded hole to 40', set
10' rock bridge and ran 10 sacks cement.


PLUGGING COMPLETE

Name of Plugging Contractor (If additional description is necessary, use BACK of this sheet)
Address KNIGHT CASING PULLING CO., INC.
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

Subscribed and sworn to before me this 17th day of July 1974



(Address) Margaret Melcher
Notary Public.

DRILLER'S LOG

Braden Drilling, Inc.
 DAVIS RANCH #1-10
 NE/4 SE/4 NW/4 Sec. 10-35-15W
 Barber County, Kansas

Commenced: November 9, 1962

Completed: November 24, 1962

Set 8 5/8" at 290' and cemented with
 150 sacks cement.

Clay	90 feet
Red bed	670
Shale	890
Shale and shells	1700
Shale and lime streaks	2075
Lime	2480
Shale	2565
Shale and lime	3085
Shale and shells	3310
Lime and shale	4230
Lime and shale streaks	4325
Lime	4920
Shale and lime	4950
Lime	5040
Cherty Lime	5070 Total depth

I, F. M. Callaway, hereby certify that this is a true and correct log
 of the above captioned well, as shown by the daily drilling reports.

F. M. Callaway
 F. M. Callaway

Subscribed and sworn to before me this 26th day of November, 1962.

My commission expires March 21, 1966

Helen Schultz
 Helen Schultz, Notary Public