

15-007-00640-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 10 Twp. 35 Rge. (E) 15 (W)

Location as "NE/CNWxSWx" or footage from lines. NE/4 SE/4 NW/4
Lease Owner Braden Drilling, Inc.
Lease Name Davis Ranch Well No. 1-10
Office Address 1206 Union National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed November 24 19 62
Application for plugging filed November 24 19 62
Application for plugging approved November 24 19 62
Plugging commenced November 24 19 62
Plugging completed November 24 19 62
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Herman E. Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
		0	890	8 5/8	890	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 800'. Set bridge plug with 1/4 sack hulls on plug. Cemented with 35 sacks Common cement. Filled hole to 40' with heavy mud. Set bridge plug with 1/4 sack hulls on plug. Cemented with 15 sacks common cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1962
11-29-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden Drilling, Inc.
Address 1206 Union National Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. M. Callaway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. M. Callaway
1206 Union National Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28 day of November, 1962.

My commission expires March 21, 1966

Walter Schmitt
Notary Public.



DRILLER'S LOG

Braden Drilling, Inc.
 DAVIS RANCH #1-10
 NE/4 SE/4 T17/4 S22. 10-35-15W
 Barber County, Kansas

Commenced: November 9, 1962

Completed: November 24, 1962

Set 8 5/8" at 596' and cemented with
 150 sacks cement.

Clay	90 feet
Red bed	670
Shale	690
Shale and shells	1760
Shale and lime streaks	2075
Lime	2480
Shale	2565
Shale and lime	3085
Shale and shells	3310
Lime and shale	4230
Lime and shale streaks	4325
Lime	4920
Shale and lime	4950
Lime	5040
Cherty Lime	5070 Total depth

I, F. N. Callaway, hereby certify that this is a true and correct log
 of the above captioned well, as shown by the daily drilling reports.

F. N. Callaway

F. N. Callaway

Subscribed and sworn to before me this 23th day of November, 1962.

My commission expires March 21, 1968

Helen Schulta

Helen Schulta, Notary Public