

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 007-22680-0000

LEASE NAME WOLGAMOTT

WELL NUMBER 2-9

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 9 TWP. 35 RGE. 14 (E) or W

COUNTY BARBER

Date Well Completed 10/23/01

Plugging Commenced 2/4/2003

Plugging Completed 2/6/2003

RECEIVED  
2-14-03  
FEB 14 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR JACK EXPLORATION, INC.

ADDRESS P.O. Box 1279, SULPHUR, OK 73086

PHONE# (580) 622-2310 OPERATORS LICENSE NO. 3080

Character of Well DEPLETED

(Oil, Gas D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-30-2003 (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? YES

Producing Formation MISSISSIPPIAN Depth to Top 4839 Bottom T.D. 5000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MISSISSIPPIAN	GAS	4805	4792	8 5/8"	284	0
		4825	4844	4 1/2"	5000	
		4876	4898			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
CIBP 4750', 2 SXS CEMENT: HOLE FULL, CUT OFF @ 3196'; 15 SKS GEL, 50 SKS PLUG @ 600';  
50 SKS PLUG @ 310'; 20 SKS FROM 40' to GL; CUT OFF 4' BELOW GL; PLATE ON TOP W/  
NAME & DATE: COVER UP, PULL ANCHOR: CLEAN UP

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor R & R WELL SERVICE License No. 4140

Address P.O. BOX 1805, WOODWARD, OK 73802

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JACK EXPLORATION, INC.

STATE OF OKLAHOMA COUNTY OF MURRAY, ss.

JAMES R. JACK

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James R. Jack

(Address) P.O. BOX 1279, SULPHUR, OK 73086

SUBSCRIBED AND SWORN TO before me this 11th day of February, 2003

[Signature]  
Notary Public

My Commission Expires: March 12, 2006