

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-20,869-0000

LEASE NAME Haskard

WELL NUMBER D-4

SPOT LOCATION CE/2 NE SW

SEC. 7 TWP. 35S RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 5-6-86

Plugging Completed 5-14-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

ADDRESS 1260 KSB Bldg. Wichita, Kansas 67202

PHONE # (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4885'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	325'	none
				4-1/2"	4884'	3348'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 25 sacks cement to 4700', shot pipe @3807', 3605', 3348' and pulled a total of 82 joints of 4-1/2" casing. Plugged surface with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 130 cement, 60/40 pos, 2% gel.

Plugging Complete
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347, Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1986
5-22-86
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 21st day of May, 1986



Irene Hoover
Notary Public

My Commission expires: _____