

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-207, 24-0000

LEASE NAME Haskard

WELL NUMBER D-2

Ft. from S Section Line

Ft. from E Section Line
 NW SE

SEC. 7 TWP. 35 RGE. 12W(E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 2-19-88

Plugging Completed 3-30-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Company, Inc.

1260 Ks. St. Bank Bldg.

ADDRESS Wichita, Kansas 67202

PHONE#(316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4918'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 325' | none |
| | | | | 4-1/2" | 4893' | 3495' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4750' and 4 sacks cement. Shot pipe @3812', 3610', 3495', pulled a total of 84 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc License No. STATE CORPORATION COMMISSION

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 31st. day of March, 1988

[Signature]
 Notary Public

My Commission Expires:



RECEIVED
 STATE CORPORATION COMMISSION

APR - 4 1988
 4-4-88

3-27-79
MAR 27 1979

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

COMMENCED:
COMPLETED:

RAM Petroleum Corporation
Union Drilling Co., Inc.
Haskard "D" #2
C NW SE Section 7-35S-12W
Barber County, Kansas
March 9, 1979
March 21, 1979

| | | | |
|------|------|----------------------------------|----------------------------|
| 0 | 830 | Red bed, sand, shale, and shells | Set 8-5/8" @325' w/250 sx. |
| 830 | 1170 | Shale | |
| 1170 | 1760 | Shale and sand | |
| 1760 | 1898 | Shale | |
| 1898 | 2317 | Shale and sand | |
| 2317 | 2516 | Shale | |
| 2516 | 2698 | Shale and lime | |
| 2698 | 2892 | Sand and shale | |
| 2892 | 3270 | Shale | |
| 3270 | 3510 | Sand and shale | |
| 3510 | 3767 | Shale | |
| 3767 | 4358 | Shale and lime | |
| 4358 | 4588 | Lime and shale | |
| 4588 | 4677 | Lime | |
| 4677 | 4817 | Lime and shale | |
| 4817 | 4843 | Lime | |
| 4843 | 4850 | Lime and chert | |
| 4850 | 4869 | Shale and lime | |
| 4869 | 4914 | Lime | |
| | 4914 | T. D. | |

We certify that the above and foregoing is a true and correct copy of the log on the Haskard "D" #2, C NW SE Section 7-35S-12W, Barber County, Kansas.

UNION DRILLING CO., INC.

R. D. Messinger
R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 23rd day of March, 1979.

My appointment expires: _____



Cynthia L. Romey
Cynthia L. Romey-Notary Public