

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER: 15-007-207, 21-0000

LEASE NAME Haskard D-1

WELL NUMBER _____

_____ Ft. from S Section Line

_____ Ft. from E Section Line
 NE SE

SEC. 7 TWP. 35 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 2-17-88

Plugging Completed 3-15-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Edmiston Oil Co., Inc.

ADDRESS 1260 Ks. St. Bank Bldg.
 Wichita, Kansas 67202

PHONE#(316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4873'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	325'	none
				4-1/2"	4872'	3302'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4750' and 4 sacks cement. Shot pipe @3803', 3302', pulled a total of 80 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas. 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 18th day of March, 1988

James Hoover
 Notary Public

My Commission Expires: _____



RECEIVED
 STATE CORPORATION COMMISSION
 3-21-88
 CONSERVATION DIVISION
 Wichita, Kansas Form CP-4
 Revised 07-86

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

COMMENCED
COMPLETED:

RAM Petroleum Corporation
Union Drilling Co., Inc.
Haskard "D" #1
C NE SE Section 7-35S-12W
Barber County, Kansas
February 24, 1979
March 8, 1979

0	371	Red bed, sand and shale	Set 8-5/8" at 325' with 225 sx.
371	1140	Red bed and shale	
1140	1183	Shale	
1183	1420	Red rock, sand and shale	
1420	1804	Shale	
1804	2178	Shale and lime	
2178	3468	Shale	
3468	3682	Shale and lime	
3682	3960	Lime and shale	
3960	4010	Lime	
4010	4330	Lime and shale	
4330	3508	Shale and lime	
4508	4700	Lime and shale	
4700	4768	Shale and lime	
4768	4805	Lime	
4805	4833	Shale and lime	
4388	4873	Lime and shale	
	4873	T. D.	

We certify that the above and foregoing is a true and correct copy of the log on the Haskard "D" #1, C NE SE Section 7-35S-12W, Barber County, Kansas.


UNION DRILLING CO., INC.

R. D. Messinger
R. D. Messinger

STATE OF KANSAS)
) SS
COUNTY, OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid County and State as of this 15th day of March, 1979.

My appointment expires:



Cynthia L. Romey
Cynthia L. Romey-Notary Public