

15-007-30264-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 2 Twp. 35 Rge. 14 W (X) (W)

Location as "NE/CNW/SW" or footage from lines NE SE
Lease Owner Summit Energy Jenkins-Ray Supply
Lease Name Sternberger Well No. 3
Office Address Box 1960 Ponca City, Oklahoma 74601
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 19
Application for plugging filed 6-11 19 71
Application for plugging approved 8-16 19 71
Plugging commenced 8-18- 19 71
Plugging completed 8-20 19 71
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	341'	none
				4 1/2"	4807'	4042'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4340 feet to 4240' feet for each plug set. with 33 sacks cement

Filled with mud; ripped pipe at 4082' and pulled. Filled with mud; pumped 100 foot cement plug from 391' to 291'; filled with mud. Put 30' cement plug from 33' to 3', cut off surface pipe 3' below surface and welded on cap inscribed with well data.

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Engineering
Address 324 Petroleum Bldg., Billings, Montana

STATE OF Oklahoma, COUNTY OF Kay, ss.
C. C. Jenkins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. C. Jenkins
Box 1960, Ponca City, Oklahoma 74601
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 19 71

Mary E. Moyer
Mary E. Moyer Notary Public.

My commission expires 10-18-72



V. W. McKeel

15-007-30264-0000

DRILLER'S WELL LOG

OPERATOR: Western Oil Fields, Inc.
P. O. Box 1137
Hobbs, New Mexico

WELL NAME: #3 Sternberger
LOCATION: 2590' fr. SL & 990' fr. EL
Section 2-35S-14W
Barber County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: 12-13-65

CASING RECORD: 8-5/8" @ 341' w/250 sx.
4-1/2" @ 4838' w/125 sx.

COMPLETED: 12-29-65

ELEVATION: 1515' DF

ROTARY TOTAL DEPTH: 4840

PRODUCTION: gas

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Sand	90
Red & Shells	341
Shale & Shells	2000
Lime & Shale	2180
Lime	2400
Lime & Shale	2605
Lime	3588
Lime & Shale	3765
Lime	4840 T.D.

RECEIVED
STATE CORPORATION COMMISSION
8-16-71
AUG 16 1971
CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, H. L. Wilson, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 10th day of January, 19 66

My Commission expires: 8-30-69

H. L. Wilson
H. L. Wilson
Julene M. Bannon
Julene M. Bannon Notary Public.

JAN 13 1966

WESTERN OIL FIELDS, INC. - HOBBBS

Rotary Drilling Contractors

K & E DRILLING, INC.

