

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 8 Twp. 35 Rge. (E) 14(W)

Location as "NE/CNW&SW&" or footage from lines NW NW NW

Lease Owner William Gruenerwald et al

Lease Name ~~XXXXXXXX~~ C. Molz Well No. 1

Office Address Room 852, 35 East Wacker Drive Chicago 1, Ill.

Character of Well (completed as Oil, Gas or Dry Hole) Dru Hole

Date well completed July 20th 19 56

Application for plugging filed July 20th 19 56

Application for plugging approved July 20th (Virbal Mr Rives) 19 56


Plugging commenced July 21st 19 56

Plugging completed July 21st 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5662 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	189	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 185 feet with heavy mud, set bridge plug 185 feet, 25 sacks cement on plug thru Drill Pipe. Filled hole 10 feet of bottom of cellar with heavy mud, set bridge plug, 10 sacks cement on plug.

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1956
7-25-56
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Patton Drilling Company, Inc.

Address 505 Orpheum Bldg. Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Robert W. Patton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert W. Patton

505 Orpheum Bldg, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 19 56

T. P. Hendrick Notary Public

My commission expires Oct 4th 1956

PLUGGING
FILE SEC 8 T 35 R 14W
BOOK PAGE 82 LINE 25

15-007-00227-0000

William Gruenerwald et al
C. Holz Well #1

Location N7 NW NW Sec. 8-T355-R14W
BARBER COUNTY, KANSAS.

Comm: 6/18/56
Comp. 7/21/56
Total Depth 5662'
Contractor Patton Drilling Co., Inc.

CASING RECORD
187' 13 3/8" Casing
Cemented with 250 Bags Cement

River Sand	20
Red Shale	187
Shale	1110
Sand Shale Anhydrite	1600
Anhydrite & Shale	1800
Lime & Shale	4279
Lime	4653
Lime & Shale	4780
Lime	4817
Lime & Shale	4822
Lime Cherty	4908
Lime	4920
Lime Cherty	4927
Lime	5018
Lime & Shale	5256
Lime	5261
Lime Cherty	5274
Lime	5374
Lime Cherty	5403
Lime	5414
Lime & Shale	5453
Shale Sandy	5597
Lime & Shale	5607
Lime	5662
Total Depth	5662

STATE OF Kansas COUNTY OF Sedgewick ss.

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

NOTARIAL COMMISSION
STATE OF KANSAS
7-25-56
NOTARIAL COMMISSION

PATTON DRILLING COMPANY, INC.

By Robert W. Patton

Subscribed and sworn to before me this 14th day of July 1956

T. P. Hendrick
Notary Public
T. P. Hendrick

My Commission Expires Oct. 4th 1956

PLUGGING
FILE SEC 8 T 35 R 14W
BOOK PAGE 82 LINE 25