

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-007-22717-00-00

LEASE NAME BENSON

WELL NUMBER 1-8

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 8 TWP. 35 RGE. 14 (E) or (W)

COUNTY BARBER

Date Well Completed 12/18/2002

Plugging Commenced 06/23/2003

Plugging Completed 06/24/2003

RECEIVED
7-14-03
JUL 14 2003

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR JACK EXPLORATION, INC.

ADDRESS P.O. BOX 1279, SULPHUR, OK 73086

PHONE (580) 622-2310 OPERATORS LICENSE NO. 3080

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05/29/2003 (date)

by DAVID P. WILLIAMS (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation MISSISSIPPIAN Depth to Top 4638 Bottom TD T.O. 5047

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Gas & Water	4860	4882	20"	65	0
		4886	4918	8 5/8"	252	0
Hertha	Gas & Water	4638	4646	4 1/2"	5046	4100

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

CIBF @ 4597.5, 2 sks cement, shot off 4100', 50 sack plug @ 600', pulled 96 lbs.
50 sk plug w/ 10 sks gel in front of plug, 50 sks @ 280', 10 sk plug @ 40' to surf.
cement fell, pumped 10 sks more, cement held.

Name of Plugging Contractor R & R Well Service License No. 33062

Address Woodward, OK

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JACK EXPLORATION, INC.

STATE OF OKLAHOMA COUNTY OF MURRAY, ss.

JAMES R. JACK (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 1279, Sulphur, OK 73086

SUBSCRIBED AND SWORN TO before me this 11th day of July, 2003

[Signature]
Notary Public

My Commission Expires: March 12, 2006