


15-007-00371-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 16 Twp. 35 S Rge. 11W 14S (W)  
Location as "NE/CNW/SW" or footage from lines 330' N of C of SL of Lot 4  
Lease Owner City Products Corporation, c/o W. J. Coppinger  
Lease Name Wolgamott Well No. 1  
Office Address 320 Union Natl Bk Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed October 11, 19 54  
Application for plugging filed Oct. 11, 19 54  
Application for plugging approved Oct. 11, 19 54  
Plugging commenced Oct. 11, 19 54  
Plugging completed Oct. 11, 19 54  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_ yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5725 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud laden fluid to 320' from top - set plug at 320' -  
cemented with 30 sax; filled hole to 35' of top; set plug; cemented  
with 15 sax to surface.

10-16-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor W. J. Coppinger  
Address 320 Union Natl Bk Bldg., Wichita Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. J. Coppinger, Operator (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. J. Coppinger  
320 Union Natl Bk Bldg., Wichita (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October 19 54

My commission expires March 7, 1956

Maguel Bronson  
Notary Public.

24-7366-S 3-53-20M



DRILLERS LOG

Owner: City Products Corporation  
 Contractor: W. J. Coppinger  
 320 Union Natl Bk Bldg.  
 Wichita, Kansas

Wolgamott #1 -  
 330' North of Center of  
 South Line of Lot 4 in  
 Section 16-35s-14w  
 Barber County, Kansas

Sand and clay	90
Red bed and sand	215
Red bed and shells	340
Red bed, shale & shells	1055
Red bed and shells	1215
Shale and shells	1700
Anhydrite	1727
Shale and shells	1775
Lime and shale	2325
Lime	2365
Lime and shale	2430
Shale	2505
Lime and shale	3760
Shale and sand	3865
Shale	3970
Shale and Lime	4057
Shale and sand	4170
Lime and shale	4283
Lime	4445
Lime and shale	4500
Lime	4595
Cherty lime	4625
Lime	4690
Lime and shale	4790
Lime	4820
Cherty lime	4850
Lime and shale	4875
Lime	4889
Chert and lime	4915
Chert	4945
Cherty lime	4960
Lime	5025
Lime and shale	5070
Shale	5145
Shale and lime	5460
Chert and shale	5480
Cherty shale	5505
Shale and lime	5530
Sand and shale	5565
Sandy shale	5645
Sandy shale and lime	5685
Sandy shale and dolomite	5725
R T D	5725

Casing:  
 13-3/8" set at 337' with 250 sax posmix  
 and 125 sax common cement

Tops: (Sample)

Anhydrite	1700
Elgin Sand	3823
Heebner	3963
Douglas Group	4056
Lansing	4168
Mississippi	4844
Mississippi Chat	4885
Kinderhook Shale	5195
Chattanooga Shale	5291
Misener Sand	5335
Maquoketa	5341
Viola	5364
Simpson Formation	5490
Wilcox #1 (Smp Snd)	5533
Wilcox #2	5650
Arbuckle	5672

R T D 5725

D & A

Commenced: Sept 15, 1954  
 Completed: Oct. 14, 1954

Elevation: 1494' R.B.  
 1491 D.F.  
 1484 Gr L.

10-16-54

STATE OF KANSAS  
 COUNTY OF SEDGWICK, ss.

I, the undersigned, being duly sworn on oath, state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

Subscribed and sworn to before me this 15th day of October, 1954.

My commission expires: March 7, 1956

*W. J. Coppinger*  
*Thayer Brown*  
 Notary Public

