

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22304-00-00
Spot: SWSWSWSW Sec/Twnshp/Rge: 29-18S-30W
75 feet from S Section Line, 329 feet from W Section Line
Lease Name: WHITING-DUTOIT Well #: 1-29
County: LANE Total Vertical Depth: 4648 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2183		CEMENTED WITH 175 SX CMT. 20 SX CMT CIRCULATED TO THE PIT.
PROD	5.5	4647	0	WITH 125 SX CMT
SURF	8.625	260		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2014 9:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: SAND PERFS T 4200' WITH 2 SX CMT. RTIH TO 2220' & CIRCULATE CMT TO 0'. CHECK BACKSIDE WITH CMT

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2014 11:30 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SAND PERFS TO 4200' WITH 2 SX CMT. RTIH TO 2220'. LOADED HOLE & CIRCULATED 200 SX CMT TO SURFACE. BACKSIDE HELD TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
4547	4550		
4361	4367		
4205	4212		
4200	4205		

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

APR 01 2014

Plugged through: TBG

RECEIVED

District: 01

RECEIVED

MAR 27 2014

KCC DODGE CITY

Signed

Nathan Willis
4/04/14
(TECHNICIAN)