

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21564-00-00
Spot: SESWSWE Sec/Twnshp/Rge: 3-32S-23W
102 feet from S Section Line, 2293 feet from E Section Line
Lease Name: BOUZIDEN Well #: 1
County: CLARK Total Vertical Depth: 6875 feet

Operator License No.: 33856
Op Name: WHITE EXPLORATION, INC.
Address: 1635 N. WATERFRONT PKWY SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	614		WITH 360 SX CMT

per FLEBANS
KCC

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/22/2013 4:00 AM
Plug Co. License No.: 34127 Plug Co. Name: TOMCAT DRILLING LLC
Proposal Revd. from: OSCAR MARTINEZ Company: TOMCAT DRILLING LLC Phone: (316) 262-8554

Proposed Plugging Method: 1ST PLUG AT 6795' WITH 50 SX CMT. 2ND PLUG AT 1210' WITH 50 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: NONE
Date/Time Plugging Completed: 10/22/2013 9:00 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report: _____ Perfs: _____

1ST PLUG AT 6795' WITH 50 SX CMT. 2ND PLUG AT 1210' WITH 50 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

KCC WICHITA
NOV 21 2013
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: DP

District: 01

Signed Nathan Willis
4/04/14
(TECHNICIAN)

RECEIVED
OCT 31 2013
KCC DODGE CITY

BWA