

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22811-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 19-9S-21W
4370 feet from S Section Line, 2270 feet from E Section Line
Lease Name: WASINGER Well #: 1
County: GRAHAM Total Vertical Depth: 3882 feet

Operator License No.: 33856

Op Name: WHITE EXPLORATION, INC.

Address: 1635 N. WATERFRONT PKWY SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3864		125 SX
SURF	8.625	227		165 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/24/2014 11:30 AM

Plug Co. License No.: 31627

Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: TERRY BAIRD

Company: WHITETAIL CRUDE, INC

Phone: (316) 641-8906

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
CIBP at 3725'.
Perforations: 3877' and 3782'. Open hole.
DV Tool at 1851' w/225 sx cement.

Plugging Proposal Received By: MARVIN MILLS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/24/2014 3:15 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3725' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 2556' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 1386' and pumped 115 sx cement. Good circulation of cement. Pulled tubing out and topped off w/25 sx cement. Tied on to back side and squeezed w/10 sx cement. Shut in pressure 300 psi.

GPS: 39.26085 -099.70666

Perfs:

Top	Bot	Thru	Comments
3877	3882		open hole

KCC WICHITA

APR 01 2014

RECEIVED

Remarks: ALLIED CEMENTING TICKET # 55171

Plugged through: TBG

District: 04

Signed

4/04/14
(TECHNICIAN)

CM

MAR 27 2014