

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20465-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 11-21S-25W
2994 feet from S Section Line, 2116 feet from E Section Line
Lease Name: GRASS C Well #: 1
County: HODGEMAN Total Vertical Depth: 4456 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3382		WITH 2 SX CMT
PROD	5.5	4429	0	WITH 125 SX CMT
SURF	8.625	225		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2014 2:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP @ 4406' WITH 2 SX CMT. PERFORATE @ 1560' WITH 50 SX CMT. TAG PLUG. PERFORATE @ 750' WITH 200 SX CMT TO SURFACE.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2014 10:30 AM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

3/21/14: CIBP @ 3382' WITH 2 SX CMT. COULD NOT GET CIBP PAST THIS POINT. PERFORATE @ 1560. PLUG WITH 50 SX CMT. PERFORATE @ 750'. CIRCULATE TO 120 SX CMT. CHECK BACKSIDE WITH 20 SX CMT & 200# PRESSURE. TOPPED OFF WITH 25 SX CMT. CMT KEPT FALLING. SDFW. 3/24/14: PERFORATE @ 360'. CIRCULATE & TOP OFF WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4429	4456		

KCC WICHITA
APR 01 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed: Daniel Sellers
4/02/14 (TECHNICIAN)

RECEIVED
MAR 25 2014
KCC DODGE CITY