

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21744-00-01  
Spot: SWSWSWNE Sec/Twnshp/Rge: 7-11S-15W  
2963 feet from S Section Line, 2362 feet from E Section Line  
Lease Name: CHRYSLER-ELLIOTT UNIT Well #: 11  
County: RUSSELL Total Vertical Depth: 3462 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3445		125 SX
SURF	8.625	273		175 SX

Well Type: EOR UIC Docket No: E26764.3 Date/Time to Plug: 03/14/2014 11:30 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: BOB GRANT Company: BEREXCO LLC Phone: (316) 772-8160

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/14/2014 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1700', 1130', 260'. Removed plug at 2894'.  
Ran tubing to 2864' and pumped 50 sx cement followed by 100 sx cement w/150 # hulls. Pulled tubing to 1390' and pumped 125 sx cement w/250 # hulls. Cement circulated out back side.  
POOH. Hooked to casing and pumped 50 sx cement. Cement circulated out braden head. Shut in and pumped cement until 300 psi was achieved.

GPS: 39.11212 -099.02751

Perfs:

Top	Bot	Thru	Comments
3136	3351		
3110	3112		

KCC WICHITA

APR 01 2014

RECEIVED

Remarks: ALLIED CEMENTING TICKET # 55162

Plugged through: TBG

District: 04

Signed RAY DINKEL (TECHNICIAN)

*cc to WCC 4/02/14*  
*4/02/14*

CM

MAR 19 2014