

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20119-00-00  
Spot: N2NWSE Sec/Twnshp/Rge: 10-10S-16W  
2310 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: CONGER - A Well #: 1  
County: ROOKS Total Vertical Depth: 3460 feet

Operator License No.: 33263  
Op Name: BOWMAN, WILLIAM F. DBA THE BILL  
Address: 2640 W RD  
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3358		125 SX
SURF	8.625	250		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2014 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: BILL BOWMAN Company: BILL BOWMAN OIL CO Phone: (785) 885-4830

Proposed DV at 810'. TOC at 470'.  
Plugging Production perforations: 3028' - 3366'.  
Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/20/2014 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes at 425', 1090' and 1600'.  
Ran tubing to 2976'. Allied pumped 11 sx gel followed by 75 sx cement w/250 # hulls. Pulled tubing to 1637'. Allied pumped 175 sx cement w/250 # hulls. Cement circulated. PTOH.  
Topped casing off w/25 sx cement. Hooked to back side and pumped 15 sx cement at 100 psi.

Perfs:

Top	Bot	Thru	Comments
3028	3366		

**KCC WICHITA**

Remarks: ALLIED CEMENTING

APR 01 2014

Plugged through: TBG

RECEIVED

District: 04

Signed Richard Williams  
4/02/14 (TECHNICIAN)

CM

MAR 27 2014