

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-05902-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 30-13S-14W  
256 feet from S Section Line, 946 feet from E Section Line  
Lease Name: ATHERTON EAST Well #: 6  
County: RUSSELL Total Vertical Depth: 3322 feet

Operator License No.: 7023  
Op Name: KLIMA WELL SERVICE, INC.  
Address: PO BOX 48  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3319		125 SX
SURF	8.625	245		200 SX

\* BIG @ 660'  
ONLY SEE  
NOTE BELOW

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2013 8:30 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE Company: KLIMA WELL SERVICE, INC. Phone: (620) 793-8888

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/26/2013 10:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Rigged up and tried to clean out well using bits, mills and washover pipe. Got outside pipe around 660'.  
Ran tubing to 660' and pumped 90 sx cement. Cement circulated. POOH. Hooked to casing and pumped 30 sx cement w/500 psi. Shut in.  
GPS: 38.88633 -098.91340

Perfs:

Top	Bot	Thru	Comments
3319	3322		OHIO

Remarks: ALLIED TICKET # 54837

Plugged through: TBG

District: 04

Signed: Ray Dinkel (TECHNICIAN)

DEC 12 2013

\*EXCEPTION GRANTED BY SB TO INV. FOR TO REACHED ONLY (660') + DUE TO NEW OPER. ASSUMING COST TO PLUG. RECEIVED

KCC WICHITA Form CP-2/3

DEC 17 2013

CM

*[Handwritten signature]*