

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40243-00-00
Spot: SWSESWNE Sec/Twnshp/Rge: 10-34S-12E
2716 feet from S Section Line, 1922 feet from E Section Line
Lease Name: COUNTY FARM Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 941 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	740		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2014 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 02/26/2014 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 850' gelled hole and spotted 20 sacks of cement. Pulled 1" and perforated casing at 500' and 350'. Ran 1" back into 500' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 159 sacks of cement were used to plug this well.

Perfs:

Remarks:

Plugged through: TBG

RECEIVED

MAR 27 2014

KCC Chanute Dist. #3

DS

KCC WICHITA

MAR 31 2014

RECEIVED

District: 03

Signed [Signature]
4/20/14 (TECHNICIAN)