

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23510-00-00
Spot: NWSWSEW Sec/Twnshp/Rge: 32-16S-24W
3237 feet from S Section Line, 3717 feet from E Section Line
Lease Name: DUBBS Well #: 3-32
County: NESS Total Vertical Depth: 4550 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		WITH 2 SX CMT
PROD	4.5	4550	0	WITH 137 SX CMT
SURF	8.625	265		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2014 10:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Revd. from: MOE SMITH Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: PULL TBG TO 1910' & CIRCULATE WITH GEL & CMT. PRESSURE 8 5/8" WITH 50 SX CMT TO 500#.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2014 12:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

CIBP @ 4450' WITH 2 SX CMT. UPPER PERFS WERE SQUEEZED OFF. CIRCULATED HOLE WITH 15 SX GEL @ 4160'. PULLED TBG TO 1930' & CIRCULATED WITH 150 SX CMT TO SURFACE. PRESSURED 8 5/8" WITH 5 SX CMT TO 500#.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Nathan Willis
3/24/14
(TECHNICIAN)

RECEIVED
MAR 13 2014
KCC DODGE CITY

KCC WICHITA
MAR 14 2014
RECEIVED

Form CP-2/3

Ray