

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20969-00-00  
Spot: SESESE Sec/Twnshp/Rge: 27-10S-18W  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: EILERS 1 Well #: 1  
County: ROOKS Total Vertical Depth: 3710 feet

Operator License No.: 5399  
Op Name: TREK AEC, LLC  
Address: 155 N MARKET STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3709		150 SX
SURF	8.625	206		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2014 12:00 PM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: THAD STARR Company: TEK AEC Phone: (620) 793-2146

Proposed: No records on Alt II  
Plugging: Fluid level 200' from surface.  
Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/700 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/07/2014 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

Perforated 2 holes each at 1950', 1425' and 900'.  
Ran tubing to 3600'. Swift services pumped 150 sx cement w/350 # hulls. Pulled tubing to 1895' and pumped 225 sx cement w/350 # hulls. Cement circulated. PTOH. Squeezed 40 sx cement. Maximum pressure 300 psi. Shut in pressure 300 psi. Hooked up to back side and pumped 50 sx cement. Maximum pressure 150 psi. Shut in pressure 150 psi

KCC WICHITA  
MAR 19 2014  
RECEIVED

Remarks: SWIFT  
Plugged through: TBG

District: 04

Signed Richard Williams  
3/24/14 (TECHNICIAN)

CM

MAR 14 2014