

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21125-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 31-6S-19W
1650 feet from S Section Line, 330 feet from W Section Line
Lease Name: OSTMEYER Well #: A-1
County: ROOKS Total Vertical Depth: 3610 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3609		175 SX
SURF	8.625	167		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/04/2014 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: THAD STARR Company: TREK AEC LLC Phone: (620) 793-2146

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Squeezed at 1978' - 2507' w/150 sx cement and 1682' w/150 sx cement.
Production perforations: 3568' - 3574' and 3299' - 3302'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2014 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Perforated at 1000'.
Ran tubing to 3567' and pumped 100 sx cement w/225 # hulls. Pulled tubing to 1620' and pumped 125 sx cement w/225 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/15 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 50 sx cement to pressure to 75 psi.

GPS: 39.48551N -099.48965W

KCC WICHITA
MAR 21 2014
RECEIVED

Remarks: SWIFT SERVICES TICKET # 25342

Plugged through: TBG

District: 04

Signed Pat Bedore
3/20/14 (TECHNICIAN) CM

MAR 18 2014