

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21166-00-00
Spot: S2NWNWSW Sec/Twnshp/Rge: 31-6S-19W
2980 feet from N Section Line, 330 feet from W Section Line
Lease Name: OSTMEYER Well #: A-2
County: ROOKS Total Vertical Depth: 3588 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3585		175 SX
SURF	8.625	168		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/03/2014 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: THAD STARR Company: TREK AEC Phone: (620) 793-2146

Proposed Method: Knocked out CIBP at 3230'.
LKC perforations: 3277' - 3281'
Arb: 3550' - 3556'
3 squeeze jobs from 1900' - 2100' w/375 sx cement
Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2014 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated at 1000'. Ran tubing to 3434'. Swift Services pumped 100 sx cement w/225 # hulls. Pulled tubing to 1655' and pumped 110 sx cement w/225 # hulls. Cement circulated. PTOH. Topped 4 1/2" casing w/25 sx cement. Casing full. Hooked up to backside and pumped 50 sx cement. Maximum pressure 150 psi. Shut in pressure 100 psi.

Perfs:

Remarks: SWIFT SERVICES

Plugged through: TBG

KCC WICHITA
MAR 10 2014
RECEIVED

District: 04

Signed Richard Williams
(TECHNICIAN)

✓ 3/24/14

CM

MAR 06 2014

Form CP-2/3