

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21164-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 31-6S-19W
990 feet from S Section Line, 330 feet from W Section Line
Lease Name: OSTMEYER Well #: A-3
County: ROOKS Total Vertical Depth: 3615 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3613		175 SX
SURF	8.625	168		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2014 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: THAD STARR Company: PROFESSIONAL PULLING SERVIC Phone: (620) 793-2146

Proposed Plugging Method:	Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls. CIBP at 3000' Perforations: 3320' - 3324', 3392' - 3396', 3471' - 3474' and 3577' - 3581'
---------------------------	--

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/27/2014 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2980' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1682' and pumped 200 sx cement w/200 # hulls. Pulled tubing. Topped off casing w/30 sx cement. Tied on to back side and squeezed w/40 sx cement. Shut in pressure 100 psi.

GPS: 39.48367 -099.48978


Perfs:

Remarks: SWIFT CEMENT CO TICKET # 25387

Plugged through: TBG

KCC WICHITA
MAR 10 2014
RECEIVED

District: 04

Signed 
3/24/14 (TECHNICIAN) CM

MAR 05 2014