

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22855-00-00
Spot: NWSENW Sec/Twnshp/Rge: 15-13S-16W
3645 feet from S Section Line, 3663 feet from E Section Line
Lease Name: RIEDEL Well #: 9
County: ELLIS Total Vertical Depth: 3660 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3660		unknown amount of cement
SURF	8.625	200		125 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/24/2014 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Control # 20140001-006
Dig Safe # KS14019965

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2014 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1680', 1100', 490' and 175'.
Ran tubing to 2480' and pumped 50 sx cement followed by 100 sx cement w/150 # hulls. Pulled tubing to 1125' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 375' and pumped 50 sx cement. Circulated cement out back side. POOH. Hooked to casing and pumped 60 sx cement. Circulated cement out braden head. Shut in.
02/25/2014- Cut off casing and topped off w/10 sx cement.

GPS: 38.92492 -099.08961

Perfs:

KCC WICHITA
MAR 10 2014
RECEIVED

Remarks: QUALITY WELL SERVICE TICKET # 5979 RIEDEL FEE FUND PROJECT CONTROL # 20140001-006

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

MAR 05 2014