

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-01318-00-00
Spot: CNWNW Sec/Twnshp/Rge: 12-35S-15W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: DAVIS RANCH Well Number: 2-12
County: BARBER Total Vertical Depth: 5025 feet

Operator License No.: 31142 Conductor Pipe: Size feet:
Operator Name: PETROLEUM PROPERTY SERVICE Surface Casing: Size 8.62 feet: 1015
Address: 155 N. MARKET, STE 1010 Production: Size 4.5 feet: 5024 163.31
WICHITA, KS 67202 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/12/2000 11:00:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1558

Proposed Plugging Method: CIBP AT 4900'. 1ST PLUG AT 1020' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. USE 15 SX GEL FOR GEL SPACER.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/12/2000 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 5004 & 4946-50. (SQUEEZED CASING LEAK AT 3571 & 3600' WITH 150 SX.) SET CIBP @ 4900' AND PUT 4 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 4 1/2" CASING. RAN 2 3/8" TUBING IN HOLE. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 1020' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1090' OF 4 1/2" (PARTED).

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 10/18/00
INV. NO. 2001060844

10-16-00
OCT 16 2000
MP

FORM 2/3