

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-19011-00-00
Spot: CSENE Sec/Twnshp/Rge: 11-35S-15W
3300 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: DAVIS RANCH Well Number: 1-11
County: BARBER Total Vertical Depth: 5062 feet

Operator License No.: 31142 Conductor Pipe: Size _____ feet:
Operator Name: PETROLEUM PROPERTY SERVICE Surface Casing: Size 8.625 feet: 933
Address: 155 N. MARKET, STE 1010 Production: Size 4.5 feet: 5062 **164.52**
WICHITA, KS 67202 **10/10** Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2000 1:00:00 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1558

Proposed Plugging Method: CIBP AT 4950 & 4 SX CMT. 1ST PLUG AT 940' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. USE 15 SX GEL FOR GEL SPACER.

Plugging Proposal Received By: MICHAEL MAIER

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 10/10/2000 4:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 5005-12'. CASING LEAK HAD BEEN SQUEEZED AT 3652 & 3546' WITH 150 SX CMT. SET CIBP AT 4950' AND PUT 4 SX CMT ON TOP OF CIBP. LOAD HOLE WITH GEL AND SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 940' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. WATER TRUCK BROKE DOWN BEFORE FINAL PLUG. WITNESSED ALL BUT FINAL PLUG.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3218' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 10/18/00
INV. NO. 2001060844

10-16-00
OCT 16 2000
MP

Form CS-200