

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20943-00-00
Spot: S2N2NW Sec/Twnshp/Rge: 17-10S-26W
4290 feet from S Section Line, 3960 feet from E Section Line
Lease Name: JOHNSON Well #: 1-17
County: SHERIDAN Total Vertical Depth: 4199 feet

Operator License No.: 34344
Op Name: CULBREATH OIL & GAS COMPANY, IN
Address: 1532 S PEORIA AVE
TULSA, OK 74120

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4199		485 SX
SURF	8.625	307		200 SX
TI	2.375	4085		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2014 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: HAROLD BELEREVIVE Company: ALLIANCE WELL SERVICE INC. Phone: (785) 627-4531

Proposed Plugging Method: DV Tool at 2268' w/360 sx cement.
Perforations: 3906' - 3910', 3896' - 3901' and 4071' - 4075'.
Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/10/2014 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4000' and pumped 90 sx cement w/200 # hulls. Pulled tubing to 2700' and pumped 90 sx cement w/250 # hulls. Pulled tubing to 1650' and pumped 130 sx cement w/150 # hulls. Good circulation of cement. Pulled tubing. Tied on to 4 1/2" casing and squeezed w/120 sx cement full. Tied on to back side and squeezed w/5 sx cement. Shut in pressure 250 psi.

GPS: 39.18756 -100.25273

Perfs:

Top	Bot	Thru	Comments
4071	7075		
3906	3910		
3896	3901		

KCC WICHITA

MAR 10 2014

RECEIVED

Remarks: SOS TICKET # 1203

Plugged through: TBG

District: 04

Signed Marvin Mills
3/20/14 (TECHNICIAN)

CM

MAR 04 2014

Form CP-2/3