

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04777-00-00
Spot: SESENE Sec/Twnshp/Rge: 35-19S-12W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: JOHANNING Well #: 1
County: BARTON Total Vertical Depth: 3331 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3328		125 SX
SURF	8.625	189		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2014 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER Phone: (620) 282-9034

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 585' and 125'.
Ran tubing and stacked out at 2800'. Pumped 50 sx cement. Pulled tubing to 2300' and pumped 13 sx gel. Pulled tubing to 1350' and pumped 80 sx cement w/100 # hulls. Pulled tubing to 600' and pumped 40 sx cement. Pulled tubing to 300'. Circulated cement to surface on casing with 70 sx cement. Tied to casing and pumped 150 sx cement. Cement did not circulate to surface.
03/07/14- Topped off well with 25 sx cement dry.
GPS: 38.35577 -098.61008

Perfs:

Top	Bot	Thru	Comments
3325	3328		
3075	3308		
2719	2900		

Remarks: ALLIED CEMENT COMPANY

Plugged through: CSG

District: 04

Signed

Bruce Rodie
KCC WICHITA 3/20/14 (TECHNICIAN) CM

KCC WICHITA 3/20/14 (TECHNICIAN) CM

MAR 18 2014

RECEIVED

MAR 12 2014

Form CP-2/3