

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01025-00-00
Spot: SESWNE Sec/Twnshp/Rge: 20-15S-12W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MEIER Well #: 1-A (7)
County: RUSSELL Total Vertical Depth: 3330 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3328		125 SX
SURF	8.625	502		325 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2014 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP Phone: (620) 282-9034

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2014 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 300', 550' and 1350'.
Ran tubing to 2950' and pumped 100 sx cement w/50 # hulls. Pulled tubing to 1450' and pumped 75 sx cement w/50 # hulls. Pulled tubing to 350' and pumped 100 sx cement. Circulated cement out braden head and back side. POOH. Hooked to casing and pressured up w/cement. Shut in pressure 300 psi.

GPS: 38.73409 -098.67668

Perfs:

Top	Bot	Thru	Comments
3289	3292		
3017	3111		

Remarks: ALLIED CEMENTING TICKET # 55045

Plugged through: TBG

District: 04

Signed

RAY DINKEL

KCC WICHITA

3/24/14

(TECHNICIAN)

CM

MAR 18 2014

RECEIVED

MAR 06 2014