

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-12257-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 29-20S-12W  
990 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: MCCULLOUGH-BRYANT B Well #: 5  
County: BARTON Total Vertical Depth: 3480 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N MARKET STE 1130  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3465		50 SX
SURF	8.625	258		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2013 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DALE MAY Company: EDMISTON OIL CO Phone: (620) 793-2222

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 11/12/2013 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 675' and 250'.  
Ran tubing to 2900' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 80 sx cement w/3 % CC and 100 # hulls. Pulled tubing to 675' and pumped 135 sx cement. Cement did not circulate. Shut down for the day.  
11/12/13-Tagged cement at 900' and pumped 175 sx cement w/200 # hulls. Pulled tubing to 150'. Circulated cement to surface w/30 sx cement. Cut off casing and surface pipe 4' below surface and topped off w/15 sx cement.

GPS: 38.28727 -098.67211

Perfs:

Top	Bot	Thru	Comments
3465	3480		

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

KCC WICHITA

3/20/14

CM

MAR 04 2014

MAR 18 2014

Form CP-2/3

RECEIVED