

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02192-00-00
Spot: E2NENW Sec/Twnshp/Rge: 17-11S-17W
660 feet from N Section Line, 2310 feet from W Section Line
Lease Name: CARMICHAEL C Well #: 7
County: ELLIS Total Vertical Depth: 3373 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3370		200 SX
SURF	10	1091		unknown

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/14/2014 10:30 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY E & P LLC Phone: (785) 737-3736

Proposed Plugging Method: Ordered 750 sx 60/40 pozmix 4% gel cement , 18 sx gel and 800 # hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/14/2014 1:50 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perf Tech perforated at 1650' - 1050'.
APS ran in hole with tubing to 3221'. Consolidated rigged to tubing and mixed and pumped 18 sx gel followed by 100 sx cement w/350 # hulls mixed in. Pulled tubing to 1650'. Consolidated rigged to tubing and pumped 345 sx cement w/450 # hulls mixed in to circulate cement up 7" casing and 10" casing. Shut in 10" casing. Pulled tubing. Topped off 7" casing w/30 sx cement. Hole standing full.

GPS: 39.10149 -099.23275
4671' FSL 2921' FEL
SE NE NE NW

Remarks: CONSOLIDATED CEMENTING TICKET # 43049

Plugged through: TBG

District: 04

Signed [Signature]
KCC WICHITA (TECHNICIAN)
MAR 18 2014
RECEIVED

CM

MAR 14 2014