

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-45765-00-00
Spot: W2SESESE Sec/Twnshp/Rge: 4-15S-13W
330 feet from S Section Line, 630 feet from E Section Line
Lease Name: LETSCH A Well #: 4
County: RUSSELL Total Vertical Depth: 3314 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3151		175 SX
SURF	8.625	521		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2014 11:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: JIM FARTHING Company: EMPIRE ENERGY Phone: (620) 282-7893

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 8 sx gel and 600 # hulls

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 02/28/2014 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1550', 750' and 250'.
Ran tubing to 2950' and pumped 5 sx gel followed by 75 sx cement w/50 # hulls. Pulled tubing to 1550' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 750' and pumped 80 sx cement. Circulated cement out back side. POOH. Hooked to casing and pumped 70 sx cement and circulated cement out braden head.

GPS: 38.77036 -098.76473

Perfs:

Remarks: QUALITY CEMENTING TICKET # 7116

Plugged through: TBG

KCC WICHITA

MAR 10 2014

RECEIVED

District: 04

Signed Ray A. Dinkel
8/22/14 (TECHNICIAN)

CM

MAR 05 2014