

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24844-00-00
Spot: S2SENESE Sec/Twnshp/Rge: 7-11S-17W
1470 feet from S Section Line, 330 feet from E Section Line
Lease Name: STEIN Well #: 8
County: ELLIS Total Vertical Depth: 3495 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3493		225 SX
SURF	8.625	1093		490 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2014 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY E & P Phone: (785) 737-3736

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 13 sx gel and 600 # hulls.
Perforations: 2986' - 2994'.
PBTB- 3416'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2014 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perf Tech perforated at 1650' and 1050'.
APS ran in hole with tubing to 3301'. Consolidated pumped 13 sx gel followed by 50 sx cement w/200 # hulls mixed in. Pulled tubing to 1650'. Consolidated mixed and pumped 360 sx cement w/150 # hulls mixed in to circulate cement up 5 1/2" casing and 8 5/8" casing. Shut in 8 5/8" casing. Pulled tubing. Topped off 5 1/2" casing with 50 sx cement. Hole standing full.

GPS: 39.10688 -099.24189
1360' FSL 317' FEL
SE SE NE SE

Remarks: CONSOLIDATED CEMENTING CO TICKET # 44420

Plugged through: TBG

District: 04

Signed _____

KCC WICHITA

(TECHNICIAN)

CM

MAR 18 2014

RECEIVED

MAR 14 2014

Form CP-2/3