

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00124-00-01
Spot: SWNENW Sec/Twnshp/Rge: 29-19S-14W
990 feet from N Section Line, 1650 feet from W Section Line
Lease Name: BURTON Well #: 1
County: BARTON Total Vertical Depth: 2417 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2395		150 SX
SURF	8.625	822		240 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/11/2014 11:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD GUNN Company: GRADY BOLDING CORP Phone: (620) 564-2240

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/11/2014 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2330' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1130' and pumped 70 sx cement w/50 # hulls. Cement circulated. Hooked up to braden head and pumped 5 sx cement and pressured up to 300 psi. POOH. Hooked to casing and pumped cement until pressure was achieved. Shut in.

GPS: 38.37347 -098.89800

Perfs:

Top	Bot	Thru	Comments
2298	2302		
2243	2247		
1768	1778		
1745	1755		

KCC WICHITA
MAR 19 2014
RECEIVED

Remarks: COPELAND ACID AND CEMENTING TICKET # 40409

Plugged through: TBG

District: 04

Signed Ray Dinkel
3/20/14 (TECHNICIAN)

CM

MAR 14 2014