

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21891-00-00  
Spot: E2W2SW Sec/Twnshp/Rge: 9-11S-16W  
1320 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: CRAIG Well #: 1-W  
County: ELLIS Total Vertical Depth: 3439 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3439		175 SX
SURF	8.625	172		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/10/2014 8:30 AM  
Plug Co. License No.: 33007 Plug Co. Name: RGN COMPANY, INC.  
Proposal Rcvd. from: ROLAND NYP Company: RGN COMPANY, INC. Phone: (785) 737-3242

Proposed R O C Bottom stage 2527'  
Plugging DV Tool at 1003' w/225 sx cement.  
Method: Production perforations: 2948' - 2958' and 3290' - 3301'  
  
Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls and 2 sx CC on side.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/10/2014 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

4 1/2" casing parted 30' down from surface. Top of cement at 152'. Casing is in bad shape. Couldn't get below 152' with tubing. Lost fluid and hole. Pumped 75 sx 60/40 pozmix 4% gel cement followed by 175 sx cement w/500 # hulls. Well on vacuum. Pumped 50 sx cement 3% CC followed by 50 sx 60/40 pozmix 4% gel cement. Maximum pressure 300 psi. Shut in pressure 250 psi.

Perfs:

Top	Bot	Thru	Comments
3290	3301		
2948	2958		

KCC WICHITA

MAR 19 2014

RECEIVED

Remarks:

Plugged through: CSG

District: 04

Signed Richard Williams  
3/20/14 (TECHNICIAN)

CM

MAR 14 2014