

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21568-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 7-17S-12W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SCHLESSIGER Well #: 3
County: BARTON Total Vertical Depth: 3410 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 1105 WALNUT
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3409		125 SX
SURF	8.625	222		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2014 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ED NEMNICH Company: K & N PETROLEUM Phone: (620) 793-4023

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% cement, 7 sx gel and 300 # hulls and 150 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2014 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 700' and 200'. Holes in casing from 1400' - 1425'.
Ran tubing to 3400' and pumped 75 sx cement. Pulled tubing to 2275' and pumped 75 sx cement. Pulled tubing to 1150' and pumped 150 sx cement. Cement started to circulate out back side. Water and mud started to circulate out braden head. POOH. Hooked to casing and pumped 125 sx cement. Circulated cement out braden head.
GPS: 38.58246 -098.70040

Remarks: COPELAND ACID AND CEMENTING TICKET # 40425

Plugged through: TBG

District: 04

Signed RAY DINKEL
KCC WICHITA (TECHNICIAN) CM
3/24/14
MAR 18 2014
RECEIVED
Form CP-2/3

MAR 06 2014